



8



ILLEGIB

ADDENDUM NO. 2
TO
SPECIFICATIONS
FOR CONSTRUCTION OF
FACILITIES REQUIRED FOR THE



STATINTL

JOB NO. 78-05327A-3 FILE NO. 8 DOC. NO. 1
IN CLASS/ (DECLASS) /CLASS CHANGED TO: TS S C RET. JUST. NO CHANGE
NEXT REV DATE - REV DATE 0879 ANSWER 2936
NO. PGS 2 CREATION DATE - ORG CODE 3535 ORG CLASS 06
REV CLASS 4 KEY COORD. AUTH: HR 70.3

UNITED STATES GOVERNMENT

DECEMBER 10, 1953

Paragraph numbers mentioned hereinafter refer to the original specification, all work shall be executed in strict accordance with that specification, and drawings mentioned therein, Addendum No. 1 and this addendum.

ATTENTION TO BIDDERS: ALL BIDDERS MUST ACKNOWLEDGE ON THE FORM OF BID RECEIPT OF THIS ADDENDUM GIVING DATE AND NUMBER OF SAME.

ITEM 9

SHOP AREA

9.4. Modification of Paragraphs (a) and (b).

(a) Ceramic tile and base on the walls shall be glazed interior tile, 6"x6"x3/8" thick, color to be selected later. Base to be of a darker shade than wall tile. Wall tile to be on all four walls of room from top of tile base to ceiling. Return the tile at the window (top, sides, and bottom) into the concrete wall 1/2" back from edge of the concrete opening. Tile to terminate against 1"x3" wood door casing with a bullnose return at top and sides of opening. Samples of each shade and color selected shall be submitted.

(b) Ceramic tile on the floor shall be 6"x6"x1/2" unglazed quarry tile except border which shall be 9" wide. Colors will be selected later and samples shall be submitted of each shade and color.